

Location: _____




R1270

COMBINED LARGE SUMP ROOF DRAIN WITH SECONDARY OVERFLOW

Specification: MIFAB® Series Series R1270 combined large sump roof drain and secondary overflow system; consisting of 24" x 42" galvanized sump receiver, two lacquered cast iron roof drain bodies with 15" diameter anchor flange, cast iron waterproofing membrane clamp rings with integral gravel stop, one 4" ABS overflow standpipe and two self-locking polyethylene dome strainers with a combined free area of 250 square inches.

Function: Used in any type of conventional or flat roofs where a safety overflow, which receives water only when the accumulation is greater than the height of the standpipe, is required to be located beside a standard roof drain. The standpipe can be adjusted to attain the desired overflow water depth. Large free area domes provide for efficient drainage of rain water and prevents debris from entering the drain line. The underdeck clamp ring is eliminated with this product because the roof drain bodies are bolted to the underside of the sump receiver and is therefore fixed. Three pieces of 5/16" x 3/4" hardware bolts and washers are provided to secure MIFAB's A2 bodies to the underside of the R1270-BP.



PIPE SIZE	BODY HEIGHT				
	NO HUB (STANDARD)	PUSH ON (P)	THREADED (T)	INSIDE CAULK (X)	PVC (-30) / ABS (-31)
2" (51)	5 3/4" (146)	5 1/2" (140)	6 1/2" (165)	6 1/2" (165)	6 3/4" (171)
3" (76)	5 3/4" (146)	5 1/2" (140)	6 5/8" (168)	6 1/2" (165)	7 1/2" (191)
4" (102)	5 3/4" (146)	5 1/2" (140)	5 1/2" (140)	6 1/2" (165)	7 5/8" (194)
5" (127)	5 3/4" (146)	5 1/2" (140)	6 5/8" (168)	6 3/4" (171)	-
6" (152)	7 1/4" (184)	5 5/8" (143)	5 5/8" (143)	6 1/2" (165)	-
8" (203)	5 7/8" (149)	N/A	N/A	(A7-8X body)	-

SUFFIX	OPTIONAL VARIATIONS
-6	Vandal proof dome (metal dome only)
-11	Acid resistant epoxy coating
-12	Galvanized metal dome
-12A	Galvanized body and membrane clamp
-12B	Galvanized metal dome and membrane clamp
-13	Galvanized body, membrane clamp and dome
-28	Stainless steel body (Type 304) (2", 3", 4")
-30	PVC socket connection body
-31	ABS socket connection body
-81	Rough bronze dome
-83	Stainless steel mesh screen over dome
-90	Threaded side outlet (2", 3", 4")
-90-NH	No Hub side outlet (cast iron only) (2", 3", 4")
(Standard)	No hub outlet
-A5	Medium sump bodies
-BA	Buy America Act compliant product

SUFFIX	OPTIONAL VARIATIONS
-C	Secondary clamp
-E	Adjustable extension
-EG	Galvanized Adjustable extension
-G	Stainless steel ballast guard
-JC	S.S. ballast guard with secondary clamp
-M	Metal dome
-M-80	Low profile silhouette aluminum dome
P	Push on outlet
-PA	Pennsylvania Steel Act compliant product
-R	2" External water dam
-RG	RoofGuard non clogging cast iron dome
T	Threaded outlet (2", 3", 4")
-U	Underdeck clamp
-U3	Underdeck clamp with cutaway side
-W-1	Water proofing flange
X	Inside caulk outlet (2", 3", 4")
-XJ	Vertical expansion joint (see R1900)

CALIFORNIA PROPOSITION 65 WARNING. This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm.

Job Name: _____ Page No: _____
 Section No: _____ Contractor: _____
 Schedule No: _____ Purchase Order No: _____